

Pipex Thermoplastic Products Pipex Packaged Pumping Station



*The packaged pumping station was manufactured offsite by Pipex. **Pictured:** factory installation of the integral shuttering system to facilitate swift and simple concrete pour on site.*

Project South West Water Lynmouth WWTW, North Devon

Location Lynmouth

Client South West Water

Contractor M J Gleeson

Scope of Work Design, supply, manufacture & delivery of a polypropylene packaged pumping station 3 meters diameter x 6.5 meters depth. The pumping station was supplied complete with integral polypropylene shuttering to facilitate swift, simple and safe site installation.

Duration Offsite factory manufacture was completed in 3 weeks. The packaged pumping station was installed on site by M J Gleeson in 1 day excluding commissioning.





Pictured: Above: PipeX chamber being offloaded and lowered into position.



Pictured: Left: internal view into PipeX chamber post offloading prior to concrete backfill. View shows prefabricated internal pipe arrangements and integral shuttering.

PDCCH041